BRUHATH BANGALORE MAHANAGARA PALIKE, DASARAHALLI

Office of the Executive Engineer Dasarahalli Division,

Schedule-B

NAME OF WORK: Maintenance of Borewell and providing motors in W.No. 13 Shettyhalli Sub Divison

Sl. No	Description of work	Unit	Qty	Rate quoted by the Contractor Sri Hemantha Kumar S E	
				In Figures (Rs.)	Amount
1	2	3	4	5	7
1	Supply of ISI mark 175mm nominal bore,plain and steel casing pipe grade of steel Fe 410 of wall thickness conforming to IS 4270-2001 and latest ammendments, electrical resistance welded steel tubes, material and conforming to IS 1387-1993 and manufactured by basic open hearth electric or basic oxygen process in random length of 5-7m both ends.threaded conforming to IS 554-1985 one end fixed with socket conforming to IS 4270-2001 and the other end with screwed pipes. All shall be responsibaly free from defects. The tubes shall be responsible straight end should be with ISI marking weighing 25.10kg/m.(exclusive of all taxes and duties).prices include Collar-Medium duty. 175mm dia x 5.4mm thick	Rmt	200.00	1296.51	259302.00
2	Providing and fixing 250mm dia PVC pipe and as per specification and directions.	Rmt	24.00	1045.0	25080.00
3	Providing and laying at site of work175mm thick MS casing caps as per IS 1239 (part-II) 1982 with all latest amendments if any for any dia. The thickness of plate used for covering one end shall be 3mm (minimum). The dimensions of caps and colars shall be strictly as per IS 1239 (Part-II) 1982 with all amendments including cost of material and labour charges for fixing, if any etc. complete with all lead and lifts and as directed by the Engineer in charge	Each	4.00	97.85	391.40
4	Supply & delivery at site brand new texmo/innoval/lubi/sabar /Atalanta/calamal/ waterman/Radha make suitable HP deep well submercible pumpset suitable for vertical installation in 150 dia borewells compressing of single stage or multistage CF pump close coupled by means of stainless steel coupling to suitable HP suitable speed totally enclosed and filled with pure drinking water squirrel cagesubmercible induction motor suitable for operation of 3Ph, 50Hz.380/440 volts AC supply fitted with required accessories such as suction, casing, suction strainers, sand guard. Non return valve etc Complete the pump and motor shall from an integral unit with all the required fittings 15HP/11KW 35stage	No	3.00	68198.07	204594.21

Signature of the Contractor

Executive Engine
Dasarahalli Divisi
BBM

5	Providing, laying & jointing GI pipes confirming to IS specification of approved make with fittings such as collars bends elbows tees nipples plugs with cuts threads using white lead & threads for joints wherever necessary as per direction including all lead & lift etc,. complete 'A' grade(excluding cost of fittings) 50mm dia GI pipe	Rmtr	1200.00	515.58	618696
6	supply of 50mm M.S collars	Each	200.00	181.26	36252.00
7	Supplying and drawing 3 core PVC Sheathed submersible pump cable manufactured with electrolytic grade copper with flexible copper conductor confirming to table 3 class 5 of IS: 8130-1984 and virgin grade PVC insulation and sheathed suitable for working voltage upto 1100 volts 4 sqmm of 56 strands 0.3mm dia	mtr	2130.00	136.99	291788.70
8	Supplying & delivery at site brand new / Essen / Lotus sunsines/Adarsh/ Gk controls best indigenous make combine energy meter-cum-control panel board unit of size 1200 x 600 x 300 mm minimum mechanically strong and vermin and water proof the unit shall have two detachable doors suitable for operation on 3ph, 50Hz, 380/440 volts, AC supply with spring loaded latch locking with a key ribs should be provided inside the door , canopy apron and louvers ventilators shall be provided the combine energy mtr cum control panel board unit suitable for operation on 3ph, 50Hz, 380/440 AC supply shall be consisted etc,. completed T panel board shall be fabricated on single unit in the above components panel board for suitable pumpset above components panel board for suitable pumpset above 6.50 HP to 15.00 HP with star delta starter (MR)	No	4.00	14060.0	56240.00
9	Fabricating supplying and mounting MS box of 16 SWG suitable for floor / wall mounting, fully weather proof with provision for better hear description, (providing with hinged front cover, equipped with tamper proof locking arrangements, with suitable size clamps with necessary cable entry pipe with gland and box should be finished 2 coats of red oxide primes paint and finally finished with approved colour enamelled metal paint etc,. complete box of 21600 sq cm	Sqcm	88000.00	0.33	29040.00
10	Providing & Fixing of clamps set and borewell cap to the pump (MR)	Set	4.00	1812.6	7250.40
11	Supply and delivery at site of brand new best make non-return valve as per IS 778/1984 with ISI Mark and as per its latest amendments,Size- 50mm . (Page no.104,item no.12.06 (a) .	No	4.00	1116.25	4465.00
12	Supply and delivery at site of brand new best make gate valve as per IS 778/1984 with ISI Mark and as per its latest amendments,Size- 50mm	No	4.00	1130.5	4522.00
13	Supply and delivery at site wrought middle steel (galvanized) 50 mm dia GI bend confirming to IS 1239-II, 1991 with latest amendments if any.	No	4.00	223.25	893.00

Signature of the Contractor

Executive Engineer
Dasarahalli Division
BBMP

14	Supply and delivery at site wrought middle steel (galvanized) 50 mm dia GI union confirming to IS 1239 II, 1991 with latest amendments if any.	No	4.00	166.25	665.00
15	Supply and delivery at site wrought middle steel (galvanized) 50 mm dia GI elbow confirming to IS 1239-II, 1991 with latest amendments if any.	No	4.00	166.25	665.00
16	Labour charges for Erection, Electrification and commissioning of Pump sets, including aligning and balancing of all items including supply and erection of two pair of supporting clamps, bore well caps, cable clips and water tight gland cable protectors, bolts, nuts, valve and gauges,tools and equipments etc., involved in the job as per specifications, with necessary tests as per specifications, with testing of as per instructions of engineer incharge of work.	Job	4.00	5528.52	22114.08
17	Labour charges for erection of indoor type panel board and meter board units with all necessary materials and labour tools and equipments including cement concrete for foundation/bed etc,complete as per specification, with testing of as per instructions of engineer incharge of work.	No	4.00	1102.77	4411.08
18	Supplying and fixing miniature circuit breakers/isolators on existing MCB distribution boards using necessary fixing materials and 'C' Type curve, indicator ON/OFF, Energy cross-3 with short circuit breaking capacity of 10k and complete wiring as required confirming to IEC 60898, 40 Amps DP	Each	4.00	1269.2	5076.80
19	Supplying and laying of L.T.U.G Cable having aluminium conductor PVC insulated shethed galvanised steel wire/ steel tape armoured cable with PVC outer sheathing 1.1 KV class 4 core 16 sqmm cable (confirming to IS 1554)	Mtr	140.00	142.5	19950.00
20	Digging of trenches of 0.6mm x 0.50 Mtrs wide refilling the trench to the required ground level and consolidating etc,. Complete sutting road surfaces (As per Civil SR KSRB I-2,P-7)	Mtr	140.00	72.2	10108.00
21	Supplying and fixing Class-A GI Pipe on pole/ wall/drain crossing with necessary clamping arrangements for UG Cable of 1.1 KV class 40mm	Mtr	12.00	318.25	3819.00
22	Earthing: Supplying and fixing and wiring earth electrode for grounding circuits IC cutouts and other equipments on the meter board in the pit. The pits should be filled up with equal proportion of salt and charcoal 150mm around the pipe to complete depth. The connection from the pipe to the conduits etc. is to established through GI wire of sizes as per clause 7.3.3 of IS 732 using 12mm bolts, nuts, washers and check nuts, the pipe shall have 16 through holes of 12mm dia. (Page no.40,item no.6.1,	Job	4.00	2849.72	11398.88
23	Providing,Supplying and fixing LT cast iron potheads suitable for 1.1 KV class UG cable filled with necessary bitumen/insulating compound complete with terminals, clamps,bolts,nuts and washers etc. with necessary materials and labour tools and equipments as per instructions of engineer incharge of work. 3◆x6 Sqm	No	4.00	486.31	1945.24

Signature of the Contractor

Executive Engin
Dasarahalli Divis
BB

24	Supplying, fixing and wiring heavy duty low voltage capacitors conforming to IS 2834, 3phase 400/440 volts grade,for power Factor improvement of roating machinery like indution motor	KVAR	4.00	391.4	15[illegible]
25	Supplying and fixing of polished wood board made of not less than 15mm thick plank on both sides of not more than 2 pieces and fixing the same to wall using tapered inverted wooden plugs screws etc., Size 20 x 20 x 2.5 inches	Each	4.00	277.4	1109.60

Signature of the Contractor

Executive Engineer,
Dasarahalli Division,